

Date: 03.12.2022

## To RENAATUS PROJECTS PRIVATE LIMITED

NO. 139, VIBGYOR, Kodambakkam High Road, Nungambakkam, Chennai - 600034

S.No	Item Description	Rate	Qty	Total Amount
1	Fabrication and supplying of Steel record rack of size 7'x4'x1-1/2', 11/2" x 1/4" -60x40x5mm L angle with holes provision for 6 plates of 18 gauge CRCA sheets, with stiffness for side and down of the panels in two different colours with bolt and nuts. The rate inclusive of cost of all materials, welding charges, bending charges, labour charges, electro powder coating, transportation as applicable and supply to worksite.	9,900	75	742,500.00
2	Supplying and fixing of Intensive Care Unit bed of size 74"x35"x20" using four section bed plate form fitted with base trolley and ABS panels for head and foot panels and two leg stands are fitted with special type wheels of four nos. The frame works made only rectangular M.S tubes and four section tops are made out of perforated M.S. sheet, Back rest, knee rest, TB/RTB position maneuvered by separate screws from foot end and collapsible mat finished aluminium side railing fitted with ICU cot. S.S. IV rods are fitted at four location wherever necessary. Bed mounted on 150m dia castor with 2 breakers. The cost includes all materials, labour charges, conveyance charges, powder coating charges etc., (The ICU cot Should be got approved by the E.E before use)	34,200	65	2,223,000.00

3	Supplying of Steel Cupboard / Wardrobe of size 36" x 76" (width 18") made with 18 Gauge CR Sheet for front side, sides, top & bottom, and 20 Gauge CR Sheet for rear side, (ISI & ISO Certified) Which is profile folded at all the edges for all sides, top and bottom of cupboard. The plates for compartments (18" width - 4 No's) are made with 18 Gauge CR Sheet. It includes one locker arrangements of size 36" x 18", located at middle horizontal rack with locking arrangements bottom buse arrangements and front double leaf shutter arrangements made with the CRCA Sheet and stiffened with round bars with hinges arrangements. All metal surfaces are finished with 60 Microns power coating. The rate includes cost of necessary ornamental handles, hinges, painting, power consumption, loading, unloading, transportations to site of work and installations etc.,	13,600.00	116	1,577,600.00	
	Grand Total :			4,543,100.00	
	GST 18% :			817,758.00	
	Net Value :			5,360,858.00	